

| Annexure – II : PRICE BID- BoQ |  |      |  |               |              |
|--------------------------------|--|------|--|---------------|--------------|
| Name of the Department         |  |      | INDIAN INSTITUTE OF MANAGEMENT<br>TIRUCHIRAPPALLI                                |               |              |
| Tender No                      |  |      | IIMT/2021-22/EO/AC/04  |               |              |
| Tender Description             |  |      | Tender for supply and installation of Air Conditioners at<br>IIM Tiruchirappalli |               |              |
| Name of the Bidder             |  |      |  |               |              |
| Sl. No                         | Description of items   | Unit | Qty  | Rate per Unit | Amount (Rs.) |
| 1                              | <p>Supplying and installation of Air Conditioner including making holes in the wall and closing the same with white cement and necessary foam insulation for copper pipes etc complete.</p> <p><b><u>Specification:</u></b><br/> <b>Air Conditioner Type:</b> Split Condenser, <b>Coil:</b> Copper<br/> <b>Cooling Capacity :</b>5.2 KW (1.5 TR), <b>Color:</b> White<br/> <b>Electrical Input:</b>230V/50HZ<br/> <b>Fan Speed:</b> 3 Steps<br/> <b>Copper tubing :</b>5m or as per the installation requirement<br/> <b>Remote control:</b> Wireless with LCD display<br/> <b>Refrigerant type:</b> R22 or any other refrigerant as per current industry standard<br/> <b>Star rating:</b> 3 (Year 2021)<br/> <b>Brand:</b> Blue Star/ Carrier/ Voltas/LG/Samsung<br/>           Included stabilizer, copper pipe, cables, outlets, etc.<br/> <b>Brand of Stabilizer:</b> V Guard/Everest/Premier</p> | Nos. | 21   |               | -            |
| 2                              | <p>Supplying and installation of Air Conditioner including making holes in the wall and closing the with white cement and necessary foam insulation for copper pipes etc complete.</p> <p><b><u>Specification:</u></b><br/> <b>Air Conditioner Type:</b> Split Condenser, <b>Coil:</b> Copper<br/> <b>Cooling Capacity :</b>3.4 KW (1.0 TR), <b>Color:</b> White<br/> <b>Electrical Input:</b>230V/50HZ<br/> <b>Fan Speed:</b> 3 Steps<br/> <b>Copper tubing :</b>5m or as per the installation requirement<br/> <b>Remote control:</b> Wireless with LCD display<br/> <b>Refrigerant type:</b> R22 or any other refrigerant as per current industry standard<br/> <b>Star:</b> 3 star (Year 2021)<br/> <b>Brand:</b> Blue Star/ Carrier/ Voltas/LG/Samsung<br/>           Included stabilizer, copper pipe, cables, outlets, etc.<br/> <b>Brand of Stabilizer:</b> V Guard/Everest/Premier</p>        | Nos. | 7  |               | -            |
| Total Amount excluding GST     |  |      |  |               | -            |
| GST at 0%                      |  |      |  |               | -            |
| Total Amount including GST     |  |      |  |               | -            |