

CORRIGENDUM-I

FOR

Tender Notification No.: IIMT/2022-23/Pur/EO/GFW/61 dated: 23.11.2022


**Notice Inviting Tender for Grill fencing work for metering point at IIM
Tiruchirappalli**

Corrigendum/Amendments in the tender document

1. Please refer to the tender document for Grill fencing work for metering point at IIM Tiruchirappalli.
2. The following changes have been made in the Tender Document through this Corrigendum-I:

S. No	Modifications/Amendments/Extension
1	The last date for submission of bids extended upto 26 th December 2022 (03.00 PM)
2	The revised Price Bid has been attached herewith. The bidder should quote the rates for all the items as per the revised Price Bid.

All other points mentioned in the Tender document, and other than the above Corrigendum will remain the same.


10/12/2022

V Priya

In-Charge (Stores & Purchase)

Revised Price Bid

S. No	Description of Works	Unit	Qty	Rate per unit	Amount
1	Providing and fixing a steel work welded in built-up sections (L angle, flat and sq. tube etc..) framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using steel, etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates, and similar work, etc. complete as per standard specification.	Kgs	500		
2	Providing and applying Painting with synthetic enamel paint of approved brand and manufacture of required color to give an even shade with texture, including preparation of the surface, etc. complete as per standard specification	Sq. m	40.00		
3	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over, including getting out and disposal of excavated earth, etc. complete as per standard specification (Average Size:0.3x0.3x0.6)	Nos	12.00		
4	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:4:8 (1 Cement : 4 coarse sand (zone-III) : 8 graded stone aggregate 40 mm nominal size) etc. complete as per standard specification	cum	1.00		
5	Providing and fixing Forged spear head ornament (Height- 0.15m & 0.3m interval spacing))by welding etc. completed as per standard specification	Nos	12.00		
6	Dismantling of existing brick compound wall for a size of 6'x4' and fixing of grill including finishing the wall with CM 1:6 etc complete including removal of debris and painting match to the existing wall.The weight of the grill will be paid separately under item no.1	Job	1		
Total Amount including Supply (Delivery to IIMT), Installation, Testing, Commissioning, Labour, Packing, forwarding, Loading, unloading, freight, etc., (excluding GST)					
GST @ _____ %					
Total Amount including GST					

Priya
10/12/2022

V Priya
In-Charge (Stores & Purchase)